

FlexNet Administrator Checklist

FOR RNI RELEASE 4.2

CHECKLIST

1. RNI System Security

- A. Create Secure User Access
 - Create a custom user role
 - Configure password policy
 - Create a new user account
- B. Verify and Establish Secure System Access
 - Server Hardening was performed during RNI installation by Sensus
 - Establish SSL protection by applying a commercial certificate from a CA to the Web and Statistics servers
- C. Provision Data Encryption
 - Determine RNI Encryption Settings
 - Configure the RNI for Encryption
 - Configure encryption on the meter

2. RNI System Operation

- A. Manage Reporting in the RNI Scheduler application
 - Verify schedule engines are connected
 - Verify scheduled jobs are running (review the status)
- B. Investigate job failures
 - Determine the cause of the failure using the log file
 - Determine if a job has a pattern of failure
 - Review the definition of a job and edit accordingly
 - Manually run any adjusted jobs to review for success/failure

3. RNI System Components

- A. Perform an Electric Meter Firmware Download in the Firmware Download application
 - Prepare for the download
 - Initiate the FWDL
 - Monitor the FWDL for successful completion
- B. Perform a Water / Gas Meter Firmware Download in the Firmware Download application
 - Prepare for the download
 - Initiate the FWDL
 - Monitor the FWDL for successful completion